

LALA HARYDAL PARK — PLANTS & TREES

Category export · AI Drone Survey · DDA / DTU parameter framework

Site: Lala Harydal Park, North Delhi (DDA)

Survey date: 19 May 2026, 11:49-12:12 IST (single-date baseline)

Category: Plants & Trees

CATEGORY SCORE				
Indicator	Mean	Min	Max	Rating
Plantation Health	73.1%	52.6%	88.8%	Fair

SCENE COVERAGE (park-wide mean)			
Metric	Mean	Min	Max
Tree canopy	17%	0.7%	41.1%
Lawn cover	17.3%	2.7%	37.3%
Green cover	42%	4.6%	77.4%

DETECTOR FINDINGS				
Detector class	Records	Mean cond. %	Worst %	Condition
Tree Stem	1767	95.5	69.3	Good
Tree Canopy	2120	82.3	43.2	Good
Lawn / Grass	2903	70.3	33.9	Fair
Shrub / Hedge	1970	58.9	31.5	Poor
Dry / Dead Vegetation	363	50.3	46.9	Poor

ANOMALIES (worst first)					
Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
7	Palm avenue & lawns	Shrub / Hedge	High	31.5	Trim to line and gap-fill the shrub / hedge run.
9	Palm avenue & lawns	Shrub / Hedge	High	32.6	Trim to line and gap-fill the shrub / hedge run.
12	Formal beds & pathways	Shrub / Hedge	High	35.2	Trim to line and gap-fill the shrub / hedge run.
14	Palm avenue & lawns	Shrub / Hedge	High	35.6	Trim to line and gap-fill the shrub / hedge run.
17	Palm avenue & lawns	Shrub / Hedge	High	36.3	Trim to line and gap-fill the shrub / hedge run.
24	Palm avenue & lawns	Shrub / Hedge	High	38.7	Trim to line and gap-fill the shrub / hedge run.
27	Palm avenue & lawns	Shrub / Hedge	High	39.4	Trim to line and gap-fill the shrub / hedge run.
29	Formal beds & pathways	Shrub / Hedge	High	39.7	Trim to line and gap-fill the shrub / hedge run.
30	Palm avenue & lawns	Shrub / Hedge	High	39.8	Trim to line and gap-fill the shrub / hedge run.
33	Palm avenue & lawns	Shrub / Hedge	High	40.1	Trim to line and gap-fill the shrub / hedge run.

Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
34	Palm avenue & lawns	Lawn / Grass	High	40.1	Aerate, feed, irrigate and overseed thin areas.
35	Palm avenue & lawns	Shrub / Hedge	High	40.1	Trim to line and gap-fill the shrub / hedge run.
38	Central axis & parterre	Shrub / Hedge	High	40.6	Trim to line and gap-fill the shrub / hedge run.
43	Formal beds & pathways	Shrub / Hedge	High	41.2	Trim to line and gap-fill the shrub / hedge run.
48	Palm avenue & lawns	Shrub / Hedge	High	41.8	Trim to line and gap-fill the shrub / hedge run.
50	Palm avenue & lawns	Shrub / Hedge	High	41.9	Trim to line and gap-fill the shrub / hedge run.
51	Formal beds & pathways	Shrub / Hedge	High	41.9	Trim to line and gap-fill the shrub / hedge run.
56	Palm avenue & lawns	Shrub / Hedge	High	42.7	Trim to line and gap-fill the shrub / hedge run.
59	Palm avenue & lawns	Shrub / Hedge	High	42.9	Trim to line and gap-fill the shrub / hedge run.
62	Formal beds & pathways	Shrub / Hedge	High	43.1	Trim to line and gap-fill the shrub / hedge run.
65	Formal beds & pathways	Tree Canopy	High	43.5	Arboricultural inspection - check vigour and tree cover dieback.
67	Palm avenue & lawns	Shrub / Hedge	High	44.1	Trim to line and gap-fill the shrub / hedge run.
69	Central axis & parterre	Shrub / Hedge	High	44.4	Trim to line and gap-fill the shrub / hedge run.
71	Formal beds & pathways	Tree Canopy	High	44.5	Arboricultural inspection - check vigour and tree cover dieback.
72	Formal beds & pathways	Shrub / Hedge	High	44.6	Trim to line and gap-fill the shrub / hedge run.
73	Formal beds & pathways	Lawn / Grass	High	44.8	Aerate, feed, irrigate and overseed thin areas.
74	Palm avenue & lawns	Shrub / Hedge	High	44.9	Trim to line and gap-fill the shrub / hedge run.
78	Palm avenue & lawns	Lawn / Grass	Medium	45.5	Aerate, feed, irrigate and overseed thin areas.
80	Formal beds & pathways	Lawn / Grass	Medium	45.8	Aerate, feed, irrigate and overseed thin areas.
81	Formal beds & pathways	Shrub / Hedge	Medium	45.9	Trim to line and gap-fill the shrub / hedge run.
84	Formal beds & pathways	Shrub / Hedge	Medium	46.1	Trim to line and gap-fill the shrub / hedge run.
91	Palm avenue & lawns	Shrub / Hedge	Medium	46.3	Trim to line and gap-fill the shrub / hedge run.
90	Formal beds & pathways	Shrub / Hedge	Medium	46.3	Trim to line and gap-fill the shrub / hedge run.
92	Central axis & parterre	Shrub / Hedge	Medium	46.3	Trim to line and gap-fill the shrub / hedge run.
97	Formal beds & pathways	Lawn / Grass	Medium	46.5	Aerate, feed, irrigate and overseed thin areas.
98	Formal beds & pathways	Lawn / Grass	Medium	46.6	Aerate, feed, irrigate and overseed thin areas.

Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
100	Palm avenue & lawns	Shrub / Hedge	Medium	47	Trim to line and gap-fill the shrub / hedge run.
103	Formal beds & pathways	Shrub / Hedge	Medium	47.3	Trim to line and gap-fill the shrub / hedge run.
106	Palm avenue & lawns	Shrub / Hedge	Medium	47.4	Trim to line and gap-fill the shrub / hedge run.
108	Palm avenue & lawns	Shrub / Hedge	Medium	47.5	Trim to line and gap-fill the shrub / hedge run.

Showing the worst 40 of 139 tracked instances in this category.

RECOMMENDED ACTIONS

#	Priority	Finding	Recommended action	Owner
1	Critical	Bare and dry ground averages 15-23% of frame across all three zones and lawn cover is only 11-22%. This is the park's dominant defect and matches the site record.	Commission a turf reinstatement programme: decompact, level, top-dress and re-turf the failed areas, then correct the watering coverage that allowed them to fail. Prioritise the formal-beds zone.	Horticulture Division
2	High	Hoses are lying across the lawns rather than a fixed watering system operating, and the dry-patch pattern is uneven - consistent with manual watering that does not reach the whole ground plane.	Audit the watering layout against the dry-patch map in this report; install or repair fixed watering to the areas that are consistently missed.	Engineering / Horticulture

Generated from Lala_Hardeval_AI_Detection_Report.xlsx · DDA AI Park Monitor. Figures are the park-wide mean across 3 analysed clips, recomputed directly from the detection log rather than the workbook's own summary formulas.