

R BLOCK, ASAF ALI PARK — PLANTS & TREES

Category export · AI Drone Survey · DDA / DTU parameter framework

Site: R Block, Asaf Ali Park, Asaf Ali Road (DDA)

Survey date: 18 May 2026, 12:16-12:35 IST (single-date baseline)

Category: Plants & Trees

CATEGORY SCORE				
Indicator	Mean	Min	Max	Rating
Plantation Health	76.8%	58.5%	91.8%	Good

SCENE COVERAGE (park-wide mean)			
Metric	Mean	Min	Max
Tree canopy	25%	0%	52.9%
Lawn cover	11%	0%	35%
Green cover	50.6%	0%	84.5%

DETECTOR FINDINGS				
Detector class	Records	Mean cond. %	Worst %	Condition
Tree Stem	1853	94.3	41.7	Good
Tree Canopy	1069	84.7	66.3	Good
Lawn / Grass	434	75	33.6	Good
Shrub / Hedge	1412	69.8	43.2	Fair
Dry / Dead Vegetation	306	49.5	41.2	Poor

ANOMALIES (worst first)					
Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
11	Garden & tree canopy	Shrub / Hedge	High	43	Trim to line and gap-fill the shrub / hedge run.
12	Pavilion (close-range)	Dry / Dead Vegetation	High	44.5	Clear dry and dead material; prune out deadwood and irrigate.
13	Garden & tree canopy	Shrub / Hedge	Medium	46.2	Trim to line and gap-fill the shrub / hedge run.
15	Garden & tree canopy	Shrub / Hedge	Medium	49.1	Trim to line and gap-fill the shrub / hedge run.
16	Garden & tree canopy	Shrub / Hedge	Medium	49.7	Trim to line and gap-fill the shrub / hedge run.
17	Garden & tree canopy	Shrub / Hedge	Medium	49.8	Trim to line and gap-fill the shrub / hedge run.
18	Pavilion (close-range)	Dry / Dead Vegetation	Medium	50.1	Clear dry and dead material; prune out deadwood and irrigate.
19	Pavilion (close-range)	Dry / Dead Vegetation	Medium	50.1	Clear dry and dead material; prune out deadwood and irrigate.
20	Pavilion (close-range)	Dry / Dead Vegetation	Medium	50.4	Clear dry and dead material; prune out deadwood and irrigate.
21	Garden & tree canopy	Shrub / Hedge	Medium	50.6	Trim to line and gap-fill the shrub / hedge run.

Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
22	Garden & tree canopy	Shrub / Hedge	Medium	50.8	Trim to line and gap-fill the shrub / hedge run.
23	Pavilion (close-range)	Dry / Dead Vegetation	Medium	50.9	Clear dry and dead material; prune out deadwood and irrigate.
24	Pavilion (close-range)	Dry / Dead Vegetation	Medium	51.2	Clear dry and dead material; prune out deadwood and irrigate.
25	Pavilion (close-range)	Dry / Dead Vegetation	Medium	51.4	Clear dry and dead material; prune out deadwood and irrigate.
26	Garden & tree canopy	Shrub / Hedge	Medium	51.5	Trim to line and gap-fill the shrub / hedge run.
28	Garden & tree canopy	Shrub / Hedge	Medium	52	Trim to line and gap-fill the shrub / hedge run.
29	Garden & tree canopy	Shrub / Hedge	Medium	54	Trim to line and gap-fill the shrub / hedge run.
30	Garden & tree canopy	Lawn / Grass	Medium	54.6	Aerate, feed, irrigate and overseed thin areas.
31	Garden & tree canopy	Shrub / Hedge	Medium	54.6	Trim to line and gap-fill the shrub / hedge run.
32	Garden & tree canopy	Shrub / Hedge	Medium	55.1	Trim to line and gap-fill the shrub / hedge run.
33	Garden & tree canopy	Shrub / Hedge	Medium	55.3	Trim to line and gap-fill the shrub / hedge run.
34	Pavilion (close-range)	Shrub / Hedge	Medium	55.4	Trim to line and gap-fill the shrub / hedge run.
37	Garden & tree canopy	Shrub / Hedge	Medium	56.1	Trim to line and gap-fill the shrub / hedge run.
38	Garden & tree canopy	Shrub / Hedge	Medium	56.3	Trim to line and gap-fill the shrub / hedge run.
40	Garden & tree canopy	Shrub / Hedge	Medium	57	Trim to line and gap-fill the shrub / hedge run.
41	Garden & tree canopy	Shrub / Hedge	Medium	57.2	Trim to line and gap-fill the shrub / hedge run.
42	Garden & tree canopy	Shrub / Hedge	Medium	57.3	Trim to line and gap-fill the shrub / hedge run.
43	Garden & tree canopy	Shrub / Hedge	Medium	57.3	Trim to line and gap-fill the shrub / hedge run.
44	Garden & tree canopy	Shrub / Hedge	Medium	57.9	Trim to line and gap-fill the shrub / hedge run.
46	Garden & tree canopy	Shrub / Hedge	Medium	58.7	Trim to line and gap-fill the shrub / hedge run.
47	Garden & tree canopy	Shrub / Hedge	Medium	59.1	Trim to line and gap-fill the shrub / hedge run.
48	Pavilion (close-range)	Shrub / Hedge	Medium	59.3	Trim to line and gap-fill the shrub / hedge run.
49	Garden & tree canopy	Tree Stem	Medium	59.6	Check stem for lean, cavities or decay; make safe if unstable.

RECOMMENDED ACTIONS

#	Priority	Finding	Recommended action	Owner
---	----------	---------	--------------------	-------

#	Priority	Finding	Recommended action	Owner
3	Medium	Ground around the pavilion is bare and hard-packed (27.7% of frame) with dry plant growth, in contrast to the healthy garden zone.	Reinstate ground cover in the pavilion surrounds; relieve compaction from foot traffic and provide a defined paved apron where desire lines have formed.	Horticulture Division
5	Low	The garden zone is in good condition - 75% green cover, healthy flowering tree cover and shrubs, watering score 93.5.	Maintain the current planting regime in this zone.	Horticulture Division
6	Process	The site record describes widespread dry patches and poor lawn across this park, but Clip 1 shows healthy planting and only 4.6% bare ground. The two clips do not cover the open lawn areas where those defects were observed.	Fly the open lawn and pathway areas of R Block to capture the dry-patch evidence; the current pair of clips under-represents the park's condition.	Survey / Drone Cell

Generated from Asaf_Ali_AI_Detection_Report.xlsx · DDA AI Park Monitor. Figures are the park-wide mean across 2 analysed clips, recomputed directly from the detection log rather than the workbook's own summary formulas.