

SANJAY LAKE — INFRASTRUCTURE

Category export · AI Drone Survey · DDA / DTU parameter framework

Site: Sanjay Lake, East Delhi (DDA)

Survey date: 19 May 2026 (single-date baseline survey)

Category: Infrastructure

CATEGORY SCORE				
Indicator	Mean	Min	Max	Rating
Infrastructure	77.1%	37.4%	96.2%	Good

SCENE COVERAGE (park-wide mean)			
Metric	Mean	Min	Max
Paved area	6.3%	0%	27.3%

DETECTOR FINDINGS				
Detector class	Records	Mean cond. %	Worst %	Condition
Walking Track	556	50.6	32.3	Poor
Kerb / Edging	1368	81.9	73.2	Good
Bench	511	79.4	69.3	Good
Open Gym Equipment	1418	87.1	69.5	Good
Pathway Obstruction	0	—	—	Not observed in these clips
Paved Area	301	56.9	47.3	Poor
Excavation / Disturbed Ground	0	—	—	Not observed in these clips
Material Stockpile	0	—	—	Not observed in these clips
Construction Activity	0	—	—	Not observed in these clips

ANOMALIES (worst first)					
Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
22	Children's play area	Walking Track	High	33.5	Resurface / patch the track; restore edge definition and camber.
24	Children's play area	Walking Track	High	33.8	Resurface / patch the track; restore edge definition and camber.
35	Children's play area	Walking Track	High	35.8	Resurface / patch the track; restore edge definition and camber.
42	Children's play area	Walking Track	High	36.5	Resurface / patch the track; restore edge definition and camber.
64	Children's play area	Walking Track	High	39.6	Resurface / patch the track; restore edge definition and camber.
78	Children's play area	Walking Track	High	41	Resurface / patch the track; restore edge definition and camber.
86	Children's play area	Walking Track	High	42.6	Resurface / patch the track; restore edge definition and camber.

Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
88	Children's play area	Walking Track	High	42.7	Resurface / patch the track; restore edge definition and camber.
93	Children's play area	Walking Track	High	43.3	Resurface / patch the track; restore edge definition and camber.
104	Children's play area	Walking Track	High	44.3	Resurface / patch the track; restore edge definition and camber.
110	Children's play area	Walking Track	Medium	45.3	Resurface / patch the track; restore edge definition and camber.
113	Children's play area	Walking Track	Medium	45.5	Resurface / patch the track; restore edge definition and camber.
125	Children's play area	Walking Track	Medium	47.1	Resurface / patch the track; restore edge definition and camber.
130	Children's play area	Walking Track	Medium	47.5	Resurface / patch the track; restore edge definition and camber.
147	Children's play area	Walking Track	Medium	48.5	Resurface / patch the track; restore edge definition and camber.
153	Children's play area	Paved Area	Medium	49.3	Patch spalled or cracked paving; re-lay settled bays.
154	Children's play area	Walking Track	Medium	49.4	Resurface / patch the track; restore edge definition and camber.
157	Children's play area	Walking Track	Medium	49.7	Resurface / patch the track; restore edge definition and camber.
159	Children's play area	Walking Track	Medium	49.9	Resurface / patch the track; restore edge definition and camber.
163	Children's play area	Walking Track	Medium	50.1	Resurface / patch the track; restore edge definition and camber.
227	Children's play area	Paved Area	Medium	53.3	Patch spalled or cracked paving; re-lay settled bays.
275	Children's play area	Walking Track	Medium	56.8	Resurface / patch the track; restore edge definition and camber.
288	Children's play area	Paved Area	Medium	58.9	Patch spalled or cracked paving; re-lay settled bays.
292	Children's play area	Walking Track	Medium	59.4	Resurface / patch the track; restore edge definition and camber.

RECOMMENDED ACTIONS

#	Priority	Finding	Recommended action	Owner
5	Medium	Play and gym equipment is broadly serviceable, but several units score materially below their cluster mean on the paint-integrity index.	Inspect the lowest-scoring units listed in '7. Anomalies'; sand, prime and repaint, and check all fixings, bearings and footings.	Engineering / Works
6	Medium	Kerb and edging runs show breaks in continuity, and some walking-track segments score poorly on surface uniformity.	Reset displaced kerb stones and patch or resurface the affected track segments.	Engineering / Works

Generated from Sanjay Lake Park AI Detection Report.xlsx · DDA AI Park Monitor. Figures are the park-wide mean across 1 analysed clip, recomputed directly from the detection log rather than the workbook's own summary formulas.