

SANJAY LAKE — IRRIGATION STATUS

Category export · AI Drone Survey · DDA / DTU parameter framework

Site: Sanjay Lake, East Delhi (DDA)

Survey date: 19 May 2026 (single-date baseline survey)

Category: Irrigation Status

CATEGORY SCORE				
Indicator	Mean	Min	Max	Rating
Irrigation Efficiency	79.6%	17.8%	100%	Good

SCENE COVERAGE (park-wide mean)			
Metric	Mean	Min	Max
Bare ground	11%	0%	50.3%
Dry vegetation	0.2%	0%	2%
Waterlogging	4.5%	0%	24.6%

DETECTOR FINDINGS				
Detector class	Records	Mean cond. %	Worst %	Condition
Waterlogging	818	47.3	34.2	Poor
Bare Ground Patch	530	40.9	15.8	Poor
Dry / Dead Vegetation	80	51.4	51.2	Poor

ANOMALIES (worst first)					
Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
1	Children's play area	Bare Ground Patch	Critical	22.1	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
4	Children's play area	Bare Ground Patch	Critical	24	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
6	Children's play area	Bare Ground Patch	Critical	26.6	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
53	Children's play area	Bare Ground Patch	High	38	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
57	Children's play area	Waterlogging	High	38.6	Investigate drainage or possible leak; regrade or provide a soak pit.
80	Children's play area	Waterlogging	High	41.9	Investigate drainage or possible leak; regrade or provide a soak pit.
81	Children's play area	Bare Ground Patch	High	42.2	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
91	Children's play area	Waterlogging	High	42.8	Investigate drainage or possible leak; regrade or provide a soak pit.
92	Children's play area	Bare Ground Patch	High	42.9	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.

Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
98	Children's play area	Waterlogging	High	44	Investigate drainage or possible leak; regrade or provide a soak pit.
100	Children's play area	Waterlogging	High	44.1	Investigate drainage or possible leak; regrade or provide a soak pit.
101	Children's play area	Waterlogging	High	44.2	Investigate drainage or possible leak; regrade or provide a soak pit.
102	Children's play area	Waterlogging	High	44.2	Investigate drainage or possible leak; regrade or provide a soak pit.
107	Children's play area	Waterlogging	High	45	Investigate drainage or possible leak; regrade or provide a soak pit.
119	Children's play area	Waterlogging	Medium	46.2	Investigate drainage or possible leak; regrade or provide a soak pit.
127	Children's play area	Bare Ground Patch	Medium	47.1	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
134	Children's play area	Bare Ground Patch	Medium	47.6	Re-turf / re-seed and top-dress the exposed area; relieve compaction and re-establish ground cover.
135	Children's play area	Waterlogging	Medium	47.7	Investigate drainage or possible leak; regrade or provide a soak pit.
139	Children's play area	Waterlogging	Medium	48.1	Investigate drainage or possible leak; regrade or provide a soak pit.
150	Children's play area	Waterlogging	Medium	49	Investigate drainage or possible leak; regrade or provide a soak pit.
167	Children's play area	Waterlogging	Medium	50.3	Investigate drainage or possible leak; regrade or provide a soak pit.
168	Children's play area	Waterlogging	Medium	50.3	Investigate drainage or possible leak; regrade or provide a soak pit.
169	Children's play area	Waterlogging	Medium	50.4	Investigate drainage or possible leak; regrade or provide a soak pit.
171	Children's play area	Waterlogging	Medium	50.6	Investigate drainage or possible leak; regrade or provide a soak pit.
172	Children's play area	Waterlogging	Medium	50.6	Investigate drainage or possible leak; regrade or provide a soak pit.
173	Children's play area	Waterlogging	Medium	50.6	Investigate drainage or possible leak; regrade or provide a soak pit.
174	Children's play area	Waterlogging	Medium	50.6	Investigate drainage or possible leak; regrade or provide a soak pit.
176	Children's play area	Waterlogging	Medium	50.6	Investigate drainage or possible leak; regrade or provide a soak pit.
177	Children's play area	Waterlogging	Medium	50.7	Investigate drainage or possible leak; regrade or provide a soak pit.
178	Children's play area	Waterlogging	Medium	50.7	Investigate drainage or possible leak; regrade or provide a soak pit.
179	Children's play area	Waterlogging	Medium	50.8	Investigate drainage or possible leak; regrade or provide a soak pit.
182	Children's play area	Waterlogging	Medium	50.9	Investigate drainage or possible leak; regrade or provide a soak pit.
184	Children's play area	Waterlogging	Medium	50.9	Investigate drainage or possible leak; regrade or provide a soak pit.
186	Children's play area	Waterlogging	Medium	51	Investigate drainage or possible leak; regrade or provide a soak pit.

Priority	Zone	Anomaly	Severity	Cond. %	Suggested action
187	Children's play area	Waterlogging	Medium	51	Investigate drainage or possible leak; regrade or provide a soak pit.
188	Children's play area	Waterlogging	Medium	51	Investigate drainage or possible leak; regrade or provide a soak pit.
189	Children's play area	Waterlogging	Medium	51	Investigate drainage or possible leak; regrade or provide a soak pit.
190	Children's play area	Waterlogging	Medium	51.1	Investigate drainage or possible leak; regrade or provide a soak pit.
191	Children's play area	Waterlogging	Medium	51.1	Investigate drainage or possible leak; regrade or provide a soak pit.
192	Children's play area	Waterlogging	Medium	51.2	Investigate drainage or possible leak; regrade or provide a soak pit.

Showing the worst 40 of 58 tracked instances in this category.

RECOMMENDED ACTIONS

#	Priority	Finding	Recommended action	Owner
1	Critical	The lake is severely depleted and heavily eutrophic. Where open water is in view the algae share of the surface approaches 100%, and a large rocky bed with cracked, eroded bank is exposed.	Commission a water-body restoration plan: de-silting, inflow and nutrient-load control, aeration, and bank stabilisation with re-profiling. Treat as the park's top capital priority.	Engineering / Horticulture
2	High	Floating waste is detected on the water surface and plastic waste is scattered along the shoreline and exposed bed.	Deploy surface skimming or net booms at the inflow, and run a shoreline clearance drive; add bins at the bridge approach.	Sanitation
4	High	The play-zone surface is predominantly bare hard-packed earth with no ground cover.	Re-establish a wear-tolerant ground cover or install an impact-absorbing play surface; decompact and top-dress before the monsoon.	Horticulture Division
12	Process	Several framework sub-parameters (gates, signage, toilets, parking, drinking water points, dustbin fill state) were never in a field of view or are unresolvable at this altitude.	Add a low-altitude amenity pass at 15-25 m over built assets so signage, bins and fixtures can be read.	Survey / Drone Cell

Generated from Sanjay_Lake_Park_AI_Detection_Report.xlsx · DDA AI Park Monitor. Figures are the park-wide mean across 1 analysed clip, recomputed directly from the detection log rather than the workbook's own summary formulas.